# Engineering Tripos Part IIA Project, GD4: Civil Engineering Design Project, 2020-21

#### Leader

Dr S Stanier [1]

# **Timing and Structure**

Tuesdays 11-1pm, and Fridays 9-11am plus afternoons

# **Prerequisites**

3D1

# **Aims**

The aims of the course are to:

- To understand the major components and working principles of a quay;
- To understand astronomical tides and storm surges;
- To deduce strength parameters of soils from test data;
- To design retaining walls in complex situations using hand calculations and the finite element method;
- To specify a capping beam, fenders and bollards;
- To decide the construction procedure and calculate the project cost;
- To appreciate the multi-disciplinary nature and the environmental impact of an engineering project.

### Content

The project involves the design of an anchored sheet pile wall on one side of an estuary to create berthing for ships and retain a section of river bank for storage and traffic. It aims to show how structural, geotechnical and hydraulic concepts can be applied in the design of facilities.

#### **FORMAT**

Students normally work in groups of four, but are responsible for and author specific parts of the reports. Groups can capitalise on a broader range of ideas for the overall conceptual designs, and can deal more comprehensively with the detailed design.

#### Week 1

Site characterisation – tide and storm surge, ships, quay dimensions, soil properties.

#### Week 2

Conceptual design – selection of the quay location, possible structural forms of the quay wall and ancillary components, construction procedures, other things that need to be considered. (Interim report is due.)

#### Week 3

# Engineering Tripos Part IIA Project, GD4: Civil Engineering Design Project, 2020-21

Published on CUED undergraduate teaching site (https://teaching.eng.cam.ac.uk)

Design a sheet pile wall remaining in equilibrium under earth pressure, water pressure and surcharge exerted by cargo, vehicles and cranes.

# Week 4

Complete the detailed design of the quay wall, and decide an overall configuration of the quay together with scour prevention measures and berthing and fendering facilities. (Final report is due.)

#### Coursework

Coursework	Due date	Marks
Interim Report	4pm Tuesday 18 May 2021	30
		(15 for individual and 15 for group work)
Final report	4pm, Friday 4 June 2021	50
		(35 for individual and 15 for group work)

# **Examination Guidelines**

Please refer to Form & conduct of the examinations [2].

Last modified: 30/11/2020 09:05

**Source URL (modified on 30-11-20):** https://teaching.eng.cam.ac.uk/content/engineering-tripos-part-iia-project-gd4-civil-engineering-design-project-2020-21

#### Links

- [1] mailto:sas229@cam.ac.uk
- [2] https://teaching.eng.cam.ac.uk/content/form-conduct-examinations